NOAA-CRN/OSD-2003-0009R0UD0
June 27, 2003
DCN 0

United States Climate Reference Network (USCRN)

Functional Requirements Document

June 2003

Prepared by:

U.S. Department of Commerce
National Oceanic and Atmospheric Administration (NOAA)
National Environmental Satellite, Data, and Information Service (NESDIS)

NOAA-CRN/OSD-2003-0009R0UD0
June 27, 2003
DCN 0

United States Climate Reference Network (USCRN)

Functional Requirements Document

June 2003

Prepared by:

U.S. Department of Commerce
National Oceanic and Atmospheric Administration (NOAA)
National Environmental Satellite, Data, and Information Service (NESDIS)

Approval Page

Document Numbers:	
NOAA/NESDIS ***CRN Series*** **X040**	**NOAA-CRN/OSD-2003-0009R0UD0** **June 27, 2003** **DCN 0**

Document Title Block:

United States Climate Reference Network (USCRN)

Functional Requirements Document

PROGRAM: USCRN	**DOCUMENT RELEASE DATE:** June 27, 2003
APPROVALS	
TITLE: USCRN Program Executive Director, NCDC — Date Tom R. Karl 7/8/03 NAME: Tom Karl (NOAA/NESDIS NCDC)	TITLE: Director – Atmospheric Turbulence and Diffusion Division — Date R P Hosker Jr. 16 July '03 NAME: Ray Hosker (NOAA/OAR/ARL/ATDD)
TITLE: USCRN Acquisition Manager — Date Richard G. Reynolds 25 Jun 03 NAME: Richard G. Reynolds (NOAA/NESDIS OSD)	
TITLE: USCRN Implementation Manager — Date Michael T Young 6/26/03 NAME: Mike Young (OSD / Short & Associates)	
TITLE: USCRN NCDC Program Manager — Date Michael R. Helfert 6-27-2003 NAME: Mike Helfert (NOAA/NESDIS NCDC)	
CCB RELEASE APPROVAL: — Date 6/25/2003 NAME: Pong Yu (NOAA/NESDIS OSD Configuration Management Office)	

Document Change Notice

DCN NO.: **0**	DATE: **June 27, 2003**	PROGRAM : SYSTEM: **USCRN**	PAGE NO.: **1** of **1**

DOCUMENT TITLE:
United States Climate Reference Network (USCRN)
Functional Requirements Document

DOCUMENT NO. **NOAA-CRN/OSD-2003-0009R0UD0**

CHANGE PAGE HISTORY

No.	Page Numbers(s)	Update Instructions (Insert/Delete/Replace)*	Reason for Change
0	Complete Document	Baseline version of the document; first publication	See COMMENTS below

COMMENTS: This DCN 0 package consists of the initial NOAA/NESDIS baseline publication of this document.

NOTE:

*EXAMPLES: *"Insert change pages 6.2-6 through 6.2-9 following page 6.2-5"*
"Replace pages 3.4-1 through 3.4-10 with change pages 3.4-1 through 3.4-10b"
"Replace pages 4.5-24 with change page 4.5-24; delete pages 4.5-25 through 4.5-30"

Version Description Record

DOCUMENT TITLE:
United States Climate Reference Network (USCRN)
Functional Requirements Document

DOCUMENT NUMBERS:	SYSTEM:	DOCUMENT BASELINE ISSUE DATE:
Baseline: NOAA-CRN/OSD-2003-0009R0UD0	USCRN	Original NOAA/NESDIS Baseline: June 27, 2003

DOCUMENT CHANGE HISTORY

DCN No.	Revision/Update Nos.	Date	DCN No.	Revision/Update Nos.	Date
0	R0UD0	June 27, 2003			

NOTES:

Preface

This document comprises the National Oceanic and Atmospheric Administration (NOAA)/ National Environmental Satellite, Data, and Information Service (NESDIS) initial baseline publication of the *United States Climate Reference Network (USCRN) Functional Requirements Document* (version DCN 0, June 27, 2003, publication). The document number is NOAA-CRN/OSD-2003-0009R0UD0.

This document describes the functional and system performance requirements for the USCRN, how well the system must perform, and under what conditions the system must operate and survive. Requirements are identified for measurement parameters, communications, data processing, access, and archive for the USCRN system. Detailed system specifications are not addressed in this document nor are specific hardware, software, or communications solutions maintenance requirements.

The publication of this baseline document closes the following Document Configuration Change Request:

DocCCR-MULTI-MISC-2003-0003

NOAA/NESDIS acknowledges the efforts of the NOAA/NESDIS National Climatic Data Center (NCDC) and Short and Associates, Inc., for their preparation of the material in this document.

Future updates and revisions to this document will be produced and controlled by NOAA/NESDIS.

Table of Contents

Section 1. Introduction 1
1.1 CRN Objective 1
1.2 Purpose 1
1.3 Scope 1
1.4 Document Organization 1

Section 2. CRN Overview 2
2.1 CRN System Summary 2
2.2 CRN Unique Service Requirements 2
2.3 CRN Field Sites 2
2.4 CRN Communications Network 2
2.5 NCDC, the CRN Central Facility 2

Section 3. Filed Site Functional Requirements 3
3.1 Operating Environment 3
3.2 Parameter Requirements 3
3.2.1 Primary and Supporting Measurements 4
3.2.2 Calibration of Sensors 4
3.2.3 Raw Data Sample Rates and Hourly Reports 4
3.2.4 Air Temperature 5
3.2.5 Precipitation 5
3.2.6 Wind Speed 6
3.2.7 Global Solar Radiation 6
3.2.8 Ground Surface (Skin) Temperature 6
3.2.9 Relative Humidity 7
3.2.10 Soil Moisture and Temperature 7
3.3 Field Site Processing Requirements 7
3.3.1 Introduction 7
3.3.2 Local Programming Capability 7
3.3.3 Automatic Recovery 8
3.3.4 Site Monitoring 8
3.3.5 Sensor Ports 8
3.3.6 Security 8
3.3.7 Data Storage 8
3.3.8 Retrieval of Stored Data and Information 8
3.3.9 Processing and Storage Margin 8

Section 4. Network Communications Functional Requirements 9
4.1 Initial Performance 9
4.2 Intermediate Storage 9
4.3 Expansion Capacity 9

Section 5. NCDC Functional Requirements 10
5.1 Introduction 10
5.2 Ingest, Processing, and Storage 10
5.2.1 Ingest 10
5.2.2 Processing 10
5.2.3 Storage 10
5.3 Data Access 10
5.4 Initiate Maintenance 10

Section 6. NCDC Functional Requirements 11
6.1 Field Site Availability 11
6.2 Availability of Air Temperature and Precipitation Reports 11
6.3 All CRN Functions 11

Section 7. Documentation Requirements 12
7.1 Introduction 12
7.2 Station History Files 12
7.2.1 Site Location 12
7.2.2 Local Terrain 12
7.2.3 Sensor Complement 12
7.2.4 Field Site Processing Algorithms 12
7.2.5 Calibration History 12
7.2.6 Equipment Failure Records 13
7.2.7 Maintenance Record 13
7.3 CRN Central Processing Documentation 13
7.3.1 Quality Control Processing 13

Acronyms and Abbreviations

ASOS	Automated Surface Observing System
AWOS	Automated Weather Observing System
COOP	Cooperative Observing Network
CRN	Climate Reference Network
FRD	Functional Requirements Document
QC	Quality Control
rpm	rotations per minute
NCDC	National Climatic Data Center
NIST	National Institute of Standards and Technology
USCRN	United States Climate Reference Network
WMO	World Meteorological Organization

References

1. *Guide to Instruments and Methods of Observation, Geneva, Switzerland (WMO, 1996, Doc 8)*
2. *Federal Standard Definitions for Meteorological Services and Supporting Research*, FCM-S1-1981, Federal Coordinator for Meteorological Services and Supporting Research

Section 1.0 Introduction

1.1 CRN Objective

The objective of the United States Climate Reference Network (USCRN) is to measure, record, and report with the highest possible quality a thoroughly documented set of surface environmental observations, representative of the climate of the United States. The CRN will provide future long-term (50-100 years) high-quality observations that can be coupled to past long-term observations, and be adequate to meet the exacting demands of climate science. Reliable observations from the CRN will allow the detection of present and future climate change, and enable scientists to increase our understanding of natural and human-induced effects.

1.2 Purpose

The purpose of this Functional Requirements Document (FRD) is to present operational and performance requirements for the CRN, a highly automated climate observing system. This document provides the necessary foundation for subsequent system specifications as well as operational and support requirements documents.

1.3 Scope

This document describes the functional and system performance requirements for the CRN, how well the system must perform, and under what conditions the system must operate and survive. Requirements are identified for measurement parameters, communications, data processing, access, and archive for the CRN system.
This document does not address the following aspects of the deployed CRN system:

- Detailed system specifications
- Specific Hardware, Software, or Communications Solutions
- Maintenance Requirements

1.4 Document Organization

Section 1	Introduction
Section 2	CRN Overview
Section 3	Field Site Functional Requirements
Section 4	Network Communications Functional Requirements
Section 5	NCDC Functional Requirements
Section 6	CRN Availability Requirements

Section 2.0 CRN Overview

2.1 CRN System Summary

When fully implemented, the CRN will provide observations from approximately 300 locations. Each location will be carefully selected to capture the representative climate regions of the nation. A communications network will link each location to the National Climatic Data Center (NCDC), where the observations will be quality controlled, archived, and made readily available with their metadata to a worldwide clientele.

2.2 CRN Unique Service Requirements

The CRN will have data that extend over 50-100 years; accuracy tied to irrefutable standards [calibrations traceable to National Institute of Standards and Technology (NIST) standards]; extensive site/system documentation; routine instrument upgrades; a rigorous maintenance program; periodic instrument recalibration and/or replacement; and, when a new instrument is introduced, a mandatory one-year minimum of parallel operation with the baseline instrument for comparison at each affected site.

2.3 CRN Field Sites

Each CRN field site will record surface measurement data, compute derived values, and periodically report these values to NCDC. For each parameter, the frequency with which the raw data are recorded will be sufficient to ensure that the computed values are fully representative of each collection period. Example-derived values include maximum, minimum, averages, and standard deviations.

2.4 CRN Communications Network

The CRN will include a network communications component to connect each field site to NCDC. The network communications component will have the capacity to reliably provide the data and information from all CRN field sites to NCDC.

2.5 NCDC, the CRN Central Facility

NCDC is the “hub” of the CRN and serves as the interface between the field sites and the users of the CRN data. CRN data will flow from the network communications central interface to NCDC’s processing and storage infrastructure, and be posted to the web accessible CRN database for direct on-line access. NCDC will maintain CRN documentation on line, and use automated data quality control processes to automatically detect the need for maintenance at field sites.

Section 3.0 Field Site Functional Requirements

3.1 Operating Environment

CRN field sites will be deployed in a wide variety of climatic regimes and are required to operate virtually unattended (minimum human presence) for prolonged periods of time. They shall operate dependably while experiencing extremes in temperature, humidity, wind, precipitation (liquid and frozen), and other environmental factors. With the exception(s) stated below, the CRN field site shall operate as specified over the following environmental range:

Temperature	-60 to +60^{0}C
Relative Humidity	to 74% at 35^{0}C; to 100% at 27^{0}C
Wind	to 50 meters per second
Rain	to 30mm per minute
Freezing Rain	25mm per hour with 9 meter per second wind
Dust	Exposure to dust laden environment
Sunshine	1400 Watts per square meter at 50^{0}C
Altitude	-500 to +10,000 feet

Exception: The CRN precipitation sensor is required to operate as specified over the temperature range of -25 to +60°C.

3.2 Parameter Requirements

This section describes the initial climate observing requirements in terms of the specific parameters to be measured; measurement accuracies, ranges, and resolutions; and computed values to be reported. The installation of sensors will be guided by the recommendations in the World Meteorological Organization (WMO), 1996: *Doc 8, Guide to Instruments and Methods of Observation*, Geneva, Switzerland (Reference 1), i.e. sensors to be installed 1.5 meters above the surface of the ground. In places where there is significant snow on the ground during the winter months, sensors (bottom of the aspirated temperature shield) are to be installed at a height of 0.6 meters [two (2) feet] above the surface of the average maximum snow depth or 1.5 meters [five (5) feet] above the surface of the ground (no snow), whichever is higher. The 1.5 meters height is also consistent with the recommended height for the Automated Surface Observing System (ASOS), Automated Weather Observing System (AWOS), and U.S. Cooperative Observing Network (COOP). In all cases, safety considerations for personnel installing and maintaining the equipment and sensors must always be taken into account when designing the physical arrangement of the instrument suite.

Except for ground surface (skin) temperature, the definitions used in this section can be found in the Federal Standard Definitions for Meteorological Services and Supporting Research, FCM-S1-1981, published by the Federal Coordinator for Meteorological Services and Supporting Research (Reference 2).

3.2.1 Primary and Supporting Measurements

The primary CRN measurement parameters are air temperature and precipitation accumulation. Measurement of these two parameters is essential for the climate record, and is required at all CRN field sites. The supporting or secondary measurement parameters are wind speed, solar radiation, and ground surface (skin) temperature. (Candidate parameters for future addition include relative humidity, soil moisture, and soil temperature.) The supporting or secondary parameters contribute to improving the confidence in the observational measurements, and provide insight into the reliability and performance of the primary sensors by means of a "gross error cross check" between the various parameters measured and reported. For instance, wind speed measured in the vicinity and near the height of the precipitation gauge orifice provides useful data when reconciling total precipitation accumulations recorded under windy conditions. The supporting parameters provide concurrent information about the environment in the immediate vicinity of the field site, and aid the development of inter-site and inter-network transfer functions. The development of such transfer functions will provide a statistical relationship between measurements at a CRN site and similar measurements taken by other sites and other surface observing networks. The transfer functions are critical for examining changes in the climate signal from and among different observing sites and networks, and will more effectively and more confidently quantify the uncertainty among them.
Collecting secondary parameter data will also support new and on-going research endeavors regarding the interrelationship between surface wind speed, global solar radiation, radiative surface (skin) temperature, and air temperature.

3.2.2 Calibration of Sensors

CRN sensors shall be calibrated against existing and recognized (traceable) calibration standards. Standard methods of calibration endorsed by the NIST will be followed to the greatest extent possible by the CRN Program. For cases in which no documented NIST standards exist, alternative calibration and testing procedures can be used if documented and accepted as standards by the scientific community. Calibration procedures and standards employed will be documented. Calibration results of each sensor will be documented and available as part of the station history files.

3.2.3 Raw Data Sample Rates and Hourly Reports

The following paragraphs specify the calculated or derived values to be reported for each parameter. Calculated or derived values include averages, maximums, and minimums over specified measurement periods. The actual raw data sample rates are not specified, and are to be considered in conjunction with the time constant or responsiveness of the sensors themselves.

3.2.3.1 Sample Rates

For each parameter, the frequency with which the raw data is recorded shall be sufficient to ensure that the computed values are accurately representative of each collection period.

3.2.3.2 Hourly Reports

Where calculations are based on an hour's data, the period shall begin on the hour. Hourly data are critical for QA/QC, network performance, and to quantify the uncertainty in daily and monthly USCRN datasets. The transmission frequency and schedule is required to be programmable at each field site (see Section 3.3.2). Each hourly report shall identify the associated measurement period.

3.2.4 Air Temperature

Each CRN field site shall provide air temperature measurements. Each air temperature sensor and its supporting apparatus shall be configured to accurately reflect the ambient air temperature at the site. Provisions to eliminate exposure to precipitation and minimize measurement biases caused by solar heat loading are required.

Air temperature measurements shall meet the following requirements:

Minimum Accuracy	$\pm$ 0.3^0 C over the range -50 to +50^0 C $\pm$ 0.6^0 C over the ranges -50 to -60^0 and +50 to -60^{0}C
Resolution	0.01^0 C for the raw data 0.1^0 C for the computed five minute averages
Reported Values for Each Sensor	- Maximum hourly value (largest 5 minute average) - Minimum hourly value (lowest 5 minute average) - Average of each hour's twelve 5-minute averages - Average temperature of the hour's last five minute period

3.2.5 Precipitation

Each CRN field site shall provide precipitation measurements. For liquid precipitation, each CRN field site shall measure the vertical depth of precipitation which reaches the Earth's surface for each 15-minute interval during an hour. This is necessary to compare with existing networks and quantify possible extreme events. For frozen precipitation, each CRN field site shall measure the water equivalent depth (depth if the precipitation were in a liquid state) which reaches the Earth's surface for each 15-minute time interval. Each precipitation sensor and its supporting apparatus shall be configured to accurately reflect the precipitation (or water equivalent) accumulation in the area of the field site. Provisions to minimize both the positive and negative effects of local winds on the precipitation measurements are required.

Precipitation measurements shall meet the following requirements:

Accuracy	± 0.25 mm or ± 2% of the reported value, whichever is greater.
Minimum Capacity	600 mm.
Maximum Required Precipitation Measurement Rate	30 mm per minute
Minimum Reporting Resolution	0.25 mm.
Reported Values for Each Sensor	Precipitation accumulation value for each 15 minute period

3.2.6 Wind Speed

Each CRN field site shall provide wind speed measurements, taken from the height of the temperature sensor. Wind Speed measurements shall meet the following requirements:

Minimum Accuracy	±1 meter per second, or ±2% of the measured value, whichever is greater
Threshold	≤ 1 meter per second
Resolution for Raw Data and Reports	1 meter per second
Reported Values for Each Hour	Hourly average wind speed

3.2.7 Global Solar Radiation

Each CRN field site shall provide global solar radiation measurements. Global solar radiation is the combination of both direct and indirect (scattered or diffusely reflected) radiation falling together on a horizontal surface. Global solar radiation measurements shall meet the following requirements:

Minimum Accuracy	±70 Watts per square meter.
Minimum Resolution	10 Watts per square meter.
Reported Values for Each Hour	Hourly average value

3.2.8 Ground Surface (Skin) Temperature

Each CRN field site shall provide ground surface temperature measurements. Ground surface, or skin temperature is the effective radiative temperature of the ground surface.

Ground surface temperature measurements shall meet the following requirements:

Minimum Accuracy	$\pm 0.5^0$C.
Minimum Resolution	0.1^0C for the raw data and reported values
Reported Values for Each Hour	Hourly average value

3.2.9 Relative Humidity

CRN field sites should be installed so that relative humidity measurements can be accommodated without system redesign. Relative humidity is the ratio of the actual vapor pressure of the air to the saturation vapor pressure at the air's current temperature. The sensors used to produce raw data for relative humidity, and their supporting apparatus, shall be configured to accurately reflect the ambient air at the field site. Provisions to eliminate exposure to precipitation and minimize measurement biases caused by solar heat loading are required.

Relative humidity measurements shall meet the following requirements:

Minimum Accuracy	$\pm$ 3% over the range from 10% to 90% $\pm$ 5% below 10% and above 90%
Minimum Resolution	1% for the raw data and reported values
Reported Values for Each Hour	Average relative humidity over the hour.

3.2.10 Soil Moisture and Temperature

Reserved

3.3 Field Site Processing Requirements

3.3.1 Introduction

This section presents the functional requirements for data processing, storage, recovery, and similar functions required at each CRN field site. These processing requirements are in addition to the computation requirements stated in Section 4.2, which included calculation of averages, minimums, maximums, and other parameters.

3.3.2 Local Programming Capability

Each CRN field site shall provide local programming capabilities to include incorporation of new and revised processing algorithms, modification of sensor sample rates, addition of new sensor types, modification of transmission frequency, and modification of output message format.

3.3.3 Automatic Recovery

Should a field site lose power and the local batteries become depleted, the site shall automatically return to full operating condition within one hour following restoration of site power.

3.3.4 Site Monitoring

Each CRN field site shall transmit engineering information to provide early insight into conditions that may effect sensor measurements or require on-site maintenance. Examples of such engineering information include battery voltage and aspirated shield fan motor rotations per minute (rpm).

3.3.5 Sensor Ports

A representative CRN field site is anticipated to include an initial complement of up to 12 sensors. To accommodate both new sensor types and comparison testing, each CRN field site shall include a sufficient number of sensor interface ports to accommodate 18 sensors.

3.3.6 Security

Each CRN field site shall incorporate reasonable security provisions to prohibit unauthorized access and/or modification.

3.3.7 Data Storage

Observational Data: Each CRN field site shall store its measurements for a minimum of sixty days, in order that these data will not be lost when communications or specific processing functions are not operating correctly.

Report Information: Each CRN field site shall store its required report information for a minimum of 60 days.

3.3.8 Retrieval of Stored Data and Information

Each CRN field site shall provide an interface for local electronic extraction of any and all data and information required to be stored. This includes processing algorithms, measured observational data, computed parameters, and engineering information.

3.3.9 Processing and Storage Margin

Each CRN field site must be able to accommodate revised or additional algorithms, computation and storage of additional parameters, and increased data sample rates. Each site shall provide a minimum of 50% processing and storage margin above that necessary to support the initially installed configuration.

Section 4.0 Network Communications Functional Requirements

The CRN communications network includes the network interface device at each field site, the inclusive network transmission medium and infrastructure, and the central interface at NCDC.

4.1 Initial Performance

The CRN communications network shall have sufficient capacity to provide NCDC with the required data and information from 300 field sites within one hour.

4.2 Intermediate Storage

The CRN communications network shall retain observations from all CRN field sites. This retention is required to mitigate the effects of a temporary outage of the NCDC central interface or of the connection between NCDC and the CRN communications network. The communications network shall retain each collected observation until successful receipt at NCDC is acknowledged or for 24 hours, whichever is smaller.

4.3 Expansion Capacity

The CRN communications network shall have sufficient expansion capacity to accommodate a 200% increase to the initial field site message size from each of the 300 field sites.

Section 5.0 NCDC Functional Requirements

5.1 Introduction

NCDC is the central collection facility of the CRN, and serves as the interface between the field sites and the users of the CRN data. The Central Facility will ingest and process the reports from all CRN field sites, and make CRN products available to a worldwide clientele. Ingest, inventory, quality control, maintenance initiation, and long-term stewardship of the CRN observations will become part of the routine base activities at NCDC.

5.2 Ingest, Processing, and Storage

5.2.1 Ingest

The Central Facility shall ingest CRN reports immediately upon their arrival from the communications network central interface. Ingest shall include a highly automated "rule-based" inventory and shall report the completeness of reporting sites and parameters for each reporting cycle.

5.2.2 Processing

Central Facility processing shall incorporate automated quality control (QC) processes to detect malfunctioning sensors and support equipment, engineering information approaching predetermined thresholds, and suspect observational values. All resultant indications or "flags" shall be reported for each CRN reporting cycle.

5.2.3 Storage

The Central Facility shall place observational data, assigned QC flags, all metadata, and site station history into the NCDC permanent archive and access system. Format, design, and documentation will be in accordance with the NCDC "best access and archive practices" utilized for similar databases.

5.3 Data Access

NCDC shall provide timely access to the CRN data, station history, and all other documentation to a worldwide clientele. All CRN observational data, attached respective "flags", metadata, and all documentation shall be posted to the web-accessible CRN database for direct on-line access. Provisions for concurrent access, user presentation, and performance shall be in accordance with NCDC best practices.

5.4 Initiate Maintenance

The Central Facility inventory, quality assurance, and quality control processing system shall generate automated notifications to designated maintenance personnel. Automated notifications shall be provided when a site report is indicative of an anomaly.

6.0 CRN Availability Requirements

6.1 Field Site Availability

CRN field sites will be deployed in a wide variety of climatic regimes and required to operate virtually unattended for a prolonged period of time. Site components shall operate dependably while experiencing extremes in temperature, humidity, wind, precipitation, power anomalies, and other environmental factors. The exposed sensors, data processor, batteries, communications device, and associated support equipment shall meet robust operational and survival environmental requirements. The primary role of each CRN field site is to report the required air temperature and precipitation information. Other required functions, while important, are secondary to this primary role.

6.2 Availability of Air Temperature and Precipitation Reports

Under normal operations, the communications network will deliver each CRN field site's required air temperature and precipitation reports to NCDC in accordance with the transmission schedule. Should a site's reports not be provided to NCDC in accordance with the transmission schedule, due to intermittent or prolonged equipment or communications outages, appropriate secondary delivery methods may be used to provide delayed reports to NCDC. Each CRN field site's required air temperature and precipitation reports shall be delivered to NCDC within 30 days after the close of the month of observation with a minimum availability of 97%, and in accordance with the transmission schedule with a minimum availability of 95%. In support of these availability requirements where multiple sensors are installed for either or both of these two parameters, a majority of the sensors for each parameter shall be operating within specification, as well as all processing, storage, and output (to the network local interface) functions associated with the required reports.

6.3 All CRN Functions

All CRN field site and communications network functions associated with the delivery of air temperature and precipitation reports to NCDC shall operate in support of the availability requirements specified in Section 6.2. All other required CRN functions shall operate with a minimum availability of 90%.

Section 7.0 Documentation Requirements

7.1 Introduction

CRN data users need to know everything about how a measurement is taken and how the resulting reported observational values are computed. The CRN program will provide this information in Station History Files and CRN Central Processing Documentation.

7.2 Station History Files

Station history files shall contain complete information on each CRN field site. Although sites will be deployed with the same sensors, support equipment and physical configuration to the extent practical, each site will be unique in a number of respects upon deployment. Over time, differences among sites may expand and up to date information on each site must be kept current.

7.2.1 Site Location

Station history files shall include the current location of each measuring site. The accuracy of the site's coordinates will be within plus or minus 15 meters for latitude, longitude, and elevation (above or below sea level).

7.2.2. Local Terrain

Station history files shall include a description of any aspects of the local landscape that may affect the quality of the observations taken and reported. Any changes to the surroundings must be thoroughly described, dated, and included in the station history files within seven working days after the completion of the activity. Station history files shall include up-to-date digital photographs of the instrument site and the surrounding terrain. Where practical, satellite images of the site will be a part of the station history files.

7.2.3 Sensor Complement

Station history files shall identify the current sensor complement at each site. Detailed specifications of each sensor shall be readily available to users, either as part of the station history files or as part of the CRN system documentation.

7.2.4 Field Site Processing Algorithms

Station history files shall contain, or identify a readily available reference to, each processing algorithm inherent to or associated with each sensor and reported value. This information shall include sampling rates and all computation algorithms.

7.2.5 Calibration History

For each site, the station history files shall include the calibration history of each sensor. This information shall include the date and the results of each sensor calibration.

7.2.6 Equipment Failure Records

Station history files shall identify each site's equipment failures, how each failure was detected, and the corrective action taken. The date and time of each failure and correction shall be included.

7.2.7 Maintenance Record

Station history files shall describe all maintenance and changes to each site.

7.3 CRN Central Processing Documentation

CRN data users need to know how the data reported by each field site are processed by the central facility, and how this may affect the data that are made available.

7.3.1 Quality Control Processing

The central processing documentation shall include a general description of the quality control processing and the meaning of each flag. The detailed quality control software code shall be made available to users.

Distribution List

Loc. No.	Organization	Name	Address	Copies	
				Paper	Elec.
National Oceanic and Atmospheric Administration (NOAA)					
Library and Floor Locations					
001	NOAA OSD Library	c/o Verna Cauley	FB 4, Room 3307	1	1
344	NOAA NCDC Library	c/o Debra Braun	FED, Room 514, Asheville, NC	2	2
OSD					
010	NOAA/OSD3	Richard G. Reynolds	FB 4, Room 3308C		1
345	NOAA/OSD3	Richard Brooks	FB 4, Room 3301D	1	
NCDC					
346	NOAA/CC11	Bruce Baker	FED, Room 420, Asheville, NC		1
347	NOAA/CC21	Debra Braun	FED, Room 514, Asheville, NC		1
348	NOAA/CC2	David Easterling	FED, Room 516, Asheville, NC		1
349	NOAA/CC3	Michael Helfert	FED, Room 468, Asheville, NC		1
351	NOAA/CC	Thomas Karl	FED, Room 557C, Asheville, NC	1	1
352	NOAA/CC	Sharon LeDuc	FED, Room 557A, Asheville, NC	1	1
OAR					
353	NOAA/ARL1	Ray Hosker	P.O. Box 2456, Oak Ridge, TN	1	1
354	NOAA/ARL1	Tilden Meyers	P.O. Box 2456, Oak Ridge, TN		1
390	NOAA/ARL1	Mark E. Hall	P.O. Box 2456, Oak Ridge, TN		1
NWS					
355	NOAA/OST32	Doug Gifford	SSMC2, Room 12110	1	
NOAA NOAA / Computer Sciences Corporation (CSC)					
094	NOAA/CSC – CMO Copy	Kelly Giglio	FB 4, Room 3317	1	
096	NOAA/CSC	Linwood Hegele	FB 4, Room 3313		1
097	NOAA/CSC	Wayne Taylor	FB 4, Room 3311		1
098	NOAA/CSC – DCO Copy	c/o Elizabeth Smith	FB 4, Room 2326	2	1
101	NOAA/CSC	Pong Yu	FB 4, Room 3315		1
205	NOAA/CSC	Forrest Gray	FB 4, Room 3315A		1
NOAA / Short and Associates (S&A)					
356	S&A	Harold Bogin	FB 4, Room 3010E		1
357	S&A	James Bradley	FB 4, Room 3010E		1
359	S&A	Edwin Hiner	FB 4, Room 3010E		1
360	S&A	Edwin May	FB 4, Room 3010E		1
363	S&A	Steve Short	FB 4, Room 3010E		1
364	S&A	Michael Young	FB 4, Room 3010E	1	1
375	S&A (at NCDC)	Marjorie McGuirk	Asheville, NC	1	1

Loc. No.	Organization	Name	Address	Copies	
				Paper	Elec.
Regional Climate Centers (RCCs)					
365	Southeastern RCC	Mike Janis	Columbia, SC		1
366	High Plains RCC	Ken Hubbard	Lincoln, NB		1
367	Western RCC	Kelly Redmond	Reno, NV		1
368	Western RCC	Dick Reinhardt	Reno, NV		1
USCRN Science Panel					
391	USCRN Science Panel	Chris Firbrich	University of Oklahoma		1
392	USCRN Science Panel	Claude Duchon	University of Oklahoma		1
393	USCRN Science Panel	Dave Robinson	Rutgers University, Piscataway, NJ		1
394	USCRN Science Panel	Greg Johnson	National Water and Climate Center, Portland, OR		1
395	USCRN Science Panel	John Christy	University of Alabama, Huntsville, AL		1
396	USCRN Science Panel	Ken Kunkel	Illinois State Water Survey, Champaign, IL		1
397	USCRN Science Panel	Nolan Doeskin	Colorado State University, Fort Collins, CO		1
398	USCRN Science Panel – NOAA/NWS	Rainer Dombrowsky	NWS, W/OS7 SSMC2, Room 4210		1
			TOTAL	13	37